


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH

Locate well correctly on above
Section Plat

Rice County, Sec. 33 Twp. 21 Rge. (E) 7 (W)

Location as "NE/CNW/SW" or footage from lines SE SE

Lease Owner Nadel & Gussman

Lease Name Richhart

Well No. 1

Office Address 1714 First National Bldg., Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 6-24 1966

Application for plugging filed 7-11 1966

Application for plugging approved 19

Plugging commenced 6-24 1966

Plugging completed 6-24 1966

Reason for abandonment of well or producing formation Surface pipe parted
skidded location.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0'	245'	8 5/8"	245'	20'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cemented through 124' of drill pipe with 100 sx of common cement.

No fill up. Re-cemented through 124' of drill pipe with 135 sx common cement. Cemented to surface. completed @ 7:35 A.M.

JUL 15 1966

JUL 15 1966

7-15-66

CONSERVATION DIVISION

WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aspen Drilling Co.

Address Box 783, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Jack M. Dunham (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Jack M. Dunham

Box 783, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 12th day of July, 1966

My commission expires

August 27, 1969

Delores Strecker

Delores Strecker

Notary Public.

D R I L L E R S L O G

COMPANY Nadel & Gussman
 CONTRACTOR Aspen Drilling Co.
 LEASE NAME #1 Richhart
 LOCATION SE SE of sec. 33-T21S-R7W
 Rice County, Kansas
 ELEVATION
 CASING RECORD 6 jts. (245') 8 5/8" Surface Casing
 COMMENCED June 20-1966
 COMPLETED June 24, 1966
 ROTARY TOTAL DEPTH 1210'

<u>Formation</u>	<u>From</u>	<u>To</u>	
Sandstone	0	80	Spudded 11:45 P.M. 6-20-66.
Red Bed & Shells	80	256	12 1/4" hole to 254'. Ran
Shale	256	283	6 jts. (245') 8 5/8" OD
Red Bed	283	328	used 23# casing. Set @ 252'
Anhydrite	328	342	with 200 sx sunset. Plug
Shale & Shells	342	840	down 5:45 A.M., 6-21-66.
Shale	840	1000	Cement circulated.
Shale & Limestone	1000	1210	

Surface pipe parted skidded location.

STATE OF KANSAS
 COUNTY OF BARTON


STATE OF KANSAS

SS

COUNTY OF BARTON

JUL 15 1966
 7-15-66
 COMMISSION DIVISION
 Wichita, Kansas

The undersigned, being duly sworn on oath, states that the above statement and log are true and a correct record and log of the well drilled at the location above described.


 Jack M. Dunham, Tool Pusher

Subscribed and sworn to before me this 17th day of July, 1966.


 Delores Strecker, Notary Public

My commission expires: August 27, 1969.