

70
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 16 1965
07-16-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Sunray DX Oil Company

Complete Address: 300 Union National Bldg., Wichita, Kansas

Lease Name Muriel Gregg Well No. # 1

Location C NW SE Sec. 31 Twp. 33 Rge. 16 (E) (W) W

County Comanche Total Depth 5831'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Stickle Drilling Company

Address: 1100 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 8:00 AM Day 15th Month July Year 1965

The Above well was plugged as follows:

227' of 13 3/8" surface pipe, cement circulated with 250 sacks. Hole
was filled with drilling mud to 225', 1st cementing plug, bridged
solid with hulls on fluid at 225', and cemented with 50 sacks, through
the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged solid with hulls on fluid at 40', and cemented with 20
sacks to the base of the cellar. Rat and mouse hole bridged and cemented
with 5 sacks.

This cementing was done by Halliburton Cementing Company.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/16/65

INV. NO. 1468-W

Signed: Archie Elving
Well Plugging Supervisor