

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21454-00-00
Spot: NENW Sec/Twnshp/Rge: 27-25S-20W
4620 feet from S Section Line, 3225 feet from E Section Line
Lease/Unit Name: SCHRADER A Well Number: 1-27
County: EDWARDS Total Vertical Depth: 4849 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 453 S. WEBB RD. STE 310 PO BOX 78020
WICHITA, KS 67278

Conductor Pipe: Size feet: \$157.59
Surface Casing: Size 8.625 feet: 349
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 10/11/2001 5:50 AM
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY
Proposal Rcvd. from: DARREL KRIER Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1300' WITH 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 10/11/2001 7:30 AM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

1ST PLUG AT 1300' WITH 50 SX CMT. 2ND PLUG AT 380' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.


Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE.

Plugged through: DP

District: 01

RECEIVED
OCT 15 2001
KCC WICHITA

Signed


(TECHNICIAN)

INVOICED

DATE 10-15-01 OCT 11 2001

NO. 2002060808

Form CR-23 