

1051891

1-26

047-00148-0002
Drilled 4/15/50

API NUMBER 15-

SW NW SW, SEC. 34, T 25 S, R 20 W/E

1650 feet from S section line

4950 feet from E section line

Lease Name Groner Well # 1

County Edwards

Well Total Depth 4760 154.70 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 576

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: BEREXCO, Inc.

Name & Address P.O. Box 723

Hays, KS 67601

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 26 Month: 1 Year: 19 95

Plugging proposal received from Richard

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 5 1/2" at 4760' w/325 sx cement, Perfs at 4672-78'

1st plug sand back to 4620' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 26 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back to 4620' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 800 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2620' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

(I did not observe this plugging.)

Signed Richard W. Lacey (TECHNICIAN)

DATE 2-6-95

INV. NO. 4.216.4

JAN 30 1995

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS