

10-22-87

1 061026

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20,192 0000

NW SE, SEC. 34, T 25 S, R 24 ~~W78~~ ^{XX}

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6278

Lease Name Bleumer Well # 1

Operator: Petx Petroleum Corporation

County Ford 162.50

Name & Address 1616 Glenarm Street, Suite 1700

Well Total Depth 5000 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service License Number 6907

Address 302 Sycamore, Box 458, Ness City, KS 67560

Company to plug at: Hour: 4:30 p.m. Day: 22 Month: 10 Year: 1987

Plugging proposal received from Dan Erickson

(company name) Petx Petroleum Corporation (phone) 303-629-1098

were: 4 1/2" at 5016' PBDT 4993' Perfs at 4961-67' Elevation 2509'GL

1st plug pump 20 sx cement to perfs,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug
nad pump 150 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 22 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement to cover perfs,

2nd plug pumped 3 sx hulls, 20 sx gel, released 8 5/8" wiper plug and pumped 200
sx ATL cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used ATL cement by Allied. Recovered 2790' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-28-87

INV. NO. 18690

OCT 26 1987

Signed Paul A. Luthi
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas