

To: 1 090518
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-27
API NUMBER 13- 047-20,179 0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Operator: BEREXCO, Inc.
Name & Address: P.O. Box 723
Hays, KS 67601

App. S/2 S/2 NW SEC. 34, T 25 S, R 20 W/E
2970 feet from S section line
3960 feet from E section line
Lease Name Froetschner Well # 1
County Edwards
Well Total Depth 4688 152.36 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 281

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:05 a.m. Day: 27 Month: 1 Year: 19 95

Plugging proposal received from Richard

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

were: 4 1/2" at 4683' w/225 sx cement, Open hole 4683-88'

1st plug sand back to 50' above perms with 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls and 20 sx cement on bottom,

3rd plug shoot at 1500', run tubing to 1200' and circulate, pull tubing and pressure up,

4th plug pump 150 sx cement down 4 1/2" casing, 5th plug pump 50 sx cement down annulus.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 p.m. Day: 27 Month: 1 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug ran tubing to 4500' and spot 25 sx cement,

2nd plug shot casing at 700', ran tubing to 700', circulated 65 sx cement to surface, pulled tubing out,

3rd plug hooked onto 4 1/2" casing and pumped in 110 sx cement. Maximum pressure 500 psi and shut in 200 psi.

4th plug hooked onto backside and pumped in 30 sx cement. Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 2-1-95

INV. NO. 42117

Signed (TECHNICIAN)