

To: 1 061029
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

10-23-87
API NUMBER 15- 047-20,816 0000
NE NE, SEC. 33, T 25 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 6278

4620 feet from S section line
660 feet from E section line
Lease Name Hornung Well # 1

Operator: Petx Petroleum Corporation
Name & Address 1616 Glenarm, Suite 1700
Denver, CO 80202

County Edwards 156.00
Well Total Depth 4800 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Hembree Well Service License Number 6907
Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 3:45 p.m. Day: 23 Month: 10 Year: 1987

Plugging proposal received from Dan Erickson
(company name) Petx Petroleum Corporation (phone) 303-293-8883

were: 4 1/2" at 4815' PBD 4740' Perfs at 4720-22' Elevation 2264'GL
1st plug pump 20 sx cement to cover perfs,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8" wiper plug
and pump 100 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 23 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement to cover perfs,
2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, released 8 5/8" wiper
plug and pumped 100 sx cement.

Maximum pressure 1500 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2636' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-4-87
WV. NO. 18746

10-23 DEC 03 1987

CCT 29 1987 10-29-87
Signed Paul A. Luthi
CONSERVATION DIVISION (TECHNICIAN)
Wichita, Kansas