

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20832-00-00
Spot: NESE Sec/Twnshp/Rge: 14-27S-16W
2010 feet from S Section Line, 664 feet from E Section Line
Lease Name: HENDRICKS Well #: 2-14
County: KIOWA Total Vertical Depth: 4600 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4586	2005	WITH 200 SX CMT
SURF	8.625	406		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/01/2012 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 4540' & 4 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/03/2013 4:40 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CASING HAD 1070 PSIG GAS PRESSURE ON IT SO THE DECISION WAS MADE TO PUMP THE BOTTOM. PUMPED 200# HULLS & 35 SX COMMON CEMENT. DISPLACED TO 4400' @ 1500 PSIG. TAGGED CMT TOP @ 4390'. 1ST PLUG AT 990' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 40 SX CMT. 3RD PLUG AT 41' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4590	4596		

RECEIVED
JAN 07 2013
KCC WICHITA

Remarks: CONTROL # 20120065-001 USED 60/40 POZMIX 4% GEL BY OULAITW WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED

JAN - 4 2013

KCC DODGE CITY

Signed

Richard W. Lacey

(TECHNICIAN)

BAZ