

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20775-00-00
Spot: NENESW Sec/Twnshp/Rge: 14-14S-15W
2290 feet from S Section Line, 3008 feet from E Section Line
Lease Name: SMITH A Well #: 8
County: RUSSELL Total Vertical Depth: 3263 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S MARKET
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3261		150 sx
SURF	8.625	207		135 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2012 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-3409

Proposed
Plugging
Method:

Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/08/2012 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 280' and hung up. Worked down to 400' and hung up. Worked down to 480' and hung up. Worked tubing to 691'. Casing was balling up in front of tubing. Worked on it at 691'. Could not make any hole.
Pulled tubing to 660' and pumped 110 sx cement and 100 # hulls. Had a little circulation of cement but lost it.
WOC.
Pumped 125 sx cement w/300 # hulls.
Cement circulated.
POOH and hooked to casing. Pumped 20 sx cement at 250 psi. Shut in.
Hooked to braden head and pumped 5 sx cement at 500 psi.

GPS:38.83130 -098.95952

RECEIVED
DEC 10 2012
KCC WICHITA

Remarks: QUALITY WELL SERVICES TICKET # 5720 CONTROL # 20130013-003 SMITH A FEE FUND PROJECT.

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

NOV 29 2012