

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22254-00-00  
Spot: W2NENWNW Sec/Twnshp/Rge: 25-13S-14W  
4927 feet from S Section Line, 4397 feet from E Section Line  
Lease Name: KRUG Well #: 2-B  
County: RUSSELL Total Vertical Depth: 3337 feet

Operator License No.: 101  
Op Name: KCC FEE FUND PLUG  
Address: 130 S MARKET  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3335		150 SX CMT
SURF	8.625	259		150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2012 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD O MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-3409

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement w/600 # hulls and 11 sx gel. Perforations: 1640', 850', 500' and 310'.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 11/12/2012 12:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations at 1640', 850', 500' and 310'.  
Ran tubing to 3200' and pumped 11 sx gel followed by 50 sx cement w/200 # hulls.  
Pulled tubing to 1640' and pumped 90 sx cement w/200 # hulls.  
Pulled tubing to 820' and pumped 90 sx cement w/200 # hulls.  
Cement circulated.  
POOH. Hooked to 5 1/2" casing and pumped 155 sx cement at 100 psi.  
11/13/2012- Casing was full and cut off. Site restored.

Perfs:

RECEIVED  
DEC 03 2012  
KCC WICHITA

Remarks: QUALITY WELL SERVICES TICKET # 5722 CONTROL # 20120061-001 KRUG 2-B FEE FUND PROJECT

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

*CM*

NOV 26 2012