

District Plugging Report

API Well Number: 15-121-02416-0000

Spot: NENWNW Sec 19 Twp 19 S Rng 23 ☒ E / ☐ W

4861 Feet from ☐ N / ☒ S Line of Section

4098 Feet from ☒ E / ☐ W Line of Section

GPS: Lat: 38.387910 Long: 94.913620 Date: 6/10/12

Lease Name: Jones Trust (Stewart) Well #: STW 06

County: Miami Total Vertical Depth: 315 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>SURF - Casing</u>	<u>6.250</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>PROD - Casing</u>	<u>2.000</u>			<u>UNKNOWN</u>
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____					

Well Type: OG - Oil & Gas UIC Docket No.: _____ Date/Time to Plug: 7/6/12 / _____
 Plug Co License No.: 34664 Plug Co. Name: Big Shot, Inc.
 Proposal Rcvd from: Rodney Johnson Company Name: Big Shot, Inc Phone: (620) 203-0829

Proposed Plugging Report:

Fill well with portland cement from TD to surface.

KANSAS CORPORATION COMMISSION

AUG 01 2012

RECEIVED

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: PART - Partial

Date/Time Plugging Completed: 7/6/12 / KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
-------------------------	--------	-----	--------	------

Drill cement to 2 ft. Hit steel. Suck fluid from hole and found 2" pipe. Change drill bit. Drill down inside of 2" to 315 ft. In cement all the way. Pull out and perforate at 300 ft and 75 ft. Pump portland cement from 315 ft to surface. Pull pipe and top off well. Pump total of 6 sacks of portland cement. Well plugged.

[illegible]

Remarks	Control No. 20120021-006. Purchase order 14300-0000001241. NAD 83 by Taylor Herman. Irreg. Section
---------	--

Plugged Thru: TBG - Tubing

Plugged Due to Compliance Issue: ☐ Yes ☒ No

District: 03

(Technician)

Form: District Plugging Report -