

2-010086

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

1-12

API NUMBER: 15-155-21,373 -00-00

NW-SW-SW SECTION 15 TOWNSHIP 23 RANGE 8W
1100 FEET FROM S SECTION LINE
600 FEET FROM E SECTION LINE

RECEIVED
KANSAS CORPORATION COMMISSION

OPERATOR LICENSE #31229
OPERATOR DLB Oil & Gas, Inc.
NAME & ADDRESS 1601 NW Expressway, Suite 700
Oklahoma City, OK 73118-1401

MAR 05 1996
3-5-96

LEASE NAME: Ehling #15219
COUNTY: Reno
WELL TOTAL DEPTH: 3790' 123.18
CONDUCTOR PIPE: " @ "
SURFACE CASING: 8 5/8" @ 224'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: White & Ellis Drilling, Inc.
ADDRESS: PO Box 48848, Wichita, KS 67201-8848 LICENSE: #5420

COMPANY TO PLUG AT: HOUR: 16:45 DAY: 12 MONTH: 1 YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM: Don Demel

COMPANY NAME: White & Ellis Drilling, Inc. PHONE: 316-263-1102

WERE: Spot cement through drill pipe. Spot 35 sacks cement at 1250', 35 sacks cement at 700', 35 sacks cement at 275', and 25 sacks cement at 60'. Put 15 sacks cement in rat hole and 10 sacks cement in mouse hole.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 19:00 DAY: 12 MONTH: 1 YEAR: 1996

ACTUAL PLUGGING REPORT: Filled hole with heavy mud and spotted cement through drill pipe. Spotted 35 sacks cement at 1250', spotted 35 sacks cement at 700', spotted 35 sacks cement at 275', spotted 25 sacks cement at 60', put 15 sacks cement in rat hole and 10 sacks cement in mouse hole

REMARKS: Used 60/40 pos mix with 4% gel by Allied - Invoice #4
I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE MAR 05 1996

Michael R. Wilson
Michael R. Wilson (AGENT)

WV. NO. 44932

FORM CP-2/3
REV. 3/90

DW