

7-12 1-031502

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA STATE OFFICE BUILDING
WICHITA, KANSAS 67202

API number: 15-007-22,570 -00-00

RECEIVED
STATE CORPORATION COMMISSION
7-15-1998
JUL 15 1998
Wichita, Kansas

SE SW NW SEC. 9, 32 S, 12 W
2290 2316 feet from N section line
870 880 feet from W section line
Part 1-28-12

Operator license#4732

Lease C.H. Bain well # 1

Operator: Clay Moore

County Barber

Address: 6440 N Central Expressway
Suite 620
Dallas, TX 76206

Well total depth 3710 feet
Conductor Pipe: inch @ feet
Surface pipe: 8 5/8 inch @ 220 feet

120.58

Aband. Oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Duke Drilling Co. License#5929

Address: 310 W Central, Ste 202 Wichita, KS 67202

Company to plug at: Hour: 7:30 a.m. Day: 12 Month: July Year: 1998

Plugging proposal received from: Mike

Company: Duke Drilling Company Phone: 316-267-1331

Were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 50 sx cement, 2nd plug at 240' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement
4th plug to circulate rathole with 15 sx cement
5th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by: Steven Durrant

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:00 a.m. Day: 12 Month: July Year: 1998

Actual plugging report:

1st plug at 660' with 50 sx cement, 2nd plug at 240' with 50 sx cement,
3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement
5th plug to circulate mousehole with 10 sx cement

Remarks: Used 60/40 Pozmix 6% gel by Allied

I did()/did not(X) observe the plugging.

Steve Durrant

(agent)

Form CP-2/3

INVOICED
DATE 7-16-98
INV. NO. 50937
7-12

SEP 18 1998