

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API API NUMBER 15-033-20,620 0000
SW SE SW, Sec. 6, T 33 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

660 feet from N/S section line

1980 feet from WXX section line

Operator License # 6420

Lease Name Waite Well # 3-6

Operator: K.R.M. Petroleum Corporation
Name & 1900 Grant Street, Ste. 300
Address Denver, CO 80203

County Comanche

Well Total Depth 5330 feet 173.22

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 732

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 6:00 pm Day: 24 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Tom Harman

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 780' with 50 sx cement

2nd plug at 240' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement.

5th plug to circulate rathole with 15 sx cement. 6th plug to circulate mousehole
with 10 sx cement.

Signed Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:45 P.M. Day: 24 Month: January Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 780' with 50 sx cement, 2nd plug at 240' with 40
sx cement, 3rd plug - solid bridge - hulls - plug at 40' -- cement to surface with
10 sx cement. 5th plug to circulate rathole with 15 sx cement. 6th plug to
circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Halliburton.

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

INVOICED RECEIVED STATE CORPORATION COMMISSION
DATE 2-1-84 JAN 26 1984
INV. NO. 9303 W CONSERVATION DIVISION
1-24 Wichita, Kansas

Signed Paul A. Luthi
(TECHNICIAN)