

5020271

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-053-20,312 0000

SWSE NW SEC. 27, T. 15 S, R. 8 (W) 10

2970 feet from N(S) section line

3630 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5552

Lease Name Thielen Well # 1

Operator: Gore Oil Company

County Ellsworth 97.27

Name & Address 125 N. Market, Ste 1750

Well Total Depth 2993' feet

Wichita, Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kalsa Casing Pulling License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 10:00 AM Day: 19 Month: February Year: 1986

Plugging proposal received from Mike McCabe

(company name) Kalsa Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 2100' and cement with 5 sacks.

Squeeze hole with 5 sacks hulls, 20 sacks Bentonite, 8 5/8" plug

and 100 sacks 60/40 Pozmix w/6% gel and 3% C.C. Pump into 8 5/8"

Surface casing.

Plugging Proposal Received by Arthur J. Lomen
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:00 AM Day: 19 Month: February Year: 1986

ACTUAL PLUGGING REPORT Hole Filled with sand to 2100' and cemented with

5 sacks. Hole squeezed with 5 sacks hulls, 20 sacks Bentonite,

and 100 sacks 60/40 Pozmix w/6% gel and 3% C.C. Pumped into

8 5/8" surface casing.

5 1/2 - 2283' - 125 sacks Per F 2160-62 Max Press. 700 PSIG Close in 300 PSIG

Remarks: 1617' of 5 1/2" casing recovered Allied Ticket # 523

(If additional description is necessary, use BACK of this form.)

RECEIVED

INVOICED

DATE 3-6-86

MAR 6 - 1986

Signed Arthur J. Lomen
(TECHNICIAN)

INV. NO. 12871

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84