

**KANSAS CORPORATION
COMMISSION**

130 S. Market
Rm 2078
Wichita, KS 67226
Fax 316-337-6211

District #1 210 E Frontview Ste A Dodge City KS 67801 620-225-8888 FAX 620-225-8885
 District #2 3450 N Rock Road Bldg 600 Ste 601 Wichita KS 67226 316-630-4000 FAX 316-630-4000
 District #3 1500 W. 7th Chanute KS 66720 620-432-2300 FAX 620-432-2309
 District #4 2301 E. 13th Hays KS 67601 785-225-0550 FAX 785-625-0564
Check Appropriate District Office

Emergency Plugging Request

Company Name: Don Sims dba Don Sims Oil Request Date: January 16, 2013

Address: 2022 W Rosehill Rd City/State/Zip: Lindsborg, KS 67456

Phone #: 785-277-3031 Fax # _____

Contact Person: Don Sims title: Owner

Well Name: Lockstrom #5 OWWO API # 15-169-60001-00-01

Location: FSL _____, FEL _____, Qtr-Qtr-Qtr C NE

Section 2, Township 16, Range 4W, County: Saline County

Type of well: Oil Gas _____ SWD _____ (Docket # _____) Other _____

Casing Information: Surface Pipe 8 5/8" @ 345' Prod. Casing 5 1/2" @ 3432'

Top and Bottom Depth of Fresh and Useable Ground Water: N/A Formation name: _____

All II/squeezes in well: _____

Junk in hole? Yes No _____ Description and attempts to remove: Pull 90,000# on tubing stuck in the hole. While pulling on tubing the 5 1/2" casing parted @ 1700'

Reason for emergency plug request: Rig is over the hole, casing is parted and the tubing is stuck. Pumped water down tubing to load and circ up the backside. Holes in tubing.

Proposed plugging method: Run slim gun down tubing as far as possible & shoot off. Run back in with working string to the top of junk and spot plug. The parted 5 1/2" will be pulled and the top plug will be done from

Name of Landowner: 400' back to surface.

Has the KSONA-1 form been filed? Yes _____ No If NO when will form be sent to landowner: ASAP
Oper is working on CP-1 & KSONA-1 today.

Expected Date to plug well: 1 / 16 / 2013

District Supervisor Approval for Emergency Plug.

Don Sims dba Don Sims Oil is hereby approved to plug the Lockstrom #5 OWWO well on this day

1 / 16 / 2013.


authorized signature

The authority to plug this well does not supersede K.S.A. 55-151 but is in agreement with K.S.A. 55- _____ which states in part that the Conservation Division shall protect and prevent the waste of fresh and usable water and correlative rights. The approval to plug this well does not include an inquiry into well ownership or the requesting operator's legal right to plug the well. This approval in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.