

KCC OIL/GAS REGULATORY OFFICES

Date: 10/04/12

District: 1

Case #: \_\_\_\_\_

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 5004  
 Op Name: Vincent Oil Corporation  
 Address 1: 155 N. Market, Ste. 700  
 Address 2: \_\_\_\_\_  
 City: Wichita  
 State: KS Zip Code: 67202 -1821  
 Operator Phone #: (316) 262-3573

API Well Number: 15-057-20843-00-00  
 Spot: NE-SE-NE Sec 14 Twp 27 S Rng 24  E /  W  
 1650 Feet from  N /  S Line of Section  
 330 Feet from  E /  W Line of Section  
 GPS: Lat: 37.70140 Long: 99.90762 Date: 10/4/12  
 Lease Name: Schneweis Well #: 2-14  
 County: Ford

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Eric Hagans.

Findings:

8 5/8" was set @ 538' with 300 sx cement. 4 1/2" was set @ 5080' with 175 sx cement on the primary cementing job. Company opened the port collar @ 1540'. Allied Oil & Gas Services, LLC pumped 150 sx of cement, circulating 15 sx to the pit. Closed the port collar.

RECEIVED  
OCT 11 2012  
KCC WICHITA

Action/Recommendations:

Follow Up Required  Yes  No

Date: \_\_\_\_\_

None. Alternate II cementing requirements have been met.  
65/35 Pozmix, 6% gel by Allied Oil & Gas Services, LLC.  
GPS converted footages are 1666' FNL & 362' FEL.

Verification Sources:

Photos Taken: 0

- RBDMS
- T-1 Database
- Other: On site witness.
- KGS
- District Files
- TA Program
- Courthouse

By: Eric MacLaren  
Eric MacLaren

Retain 1 Copy District Office  
Send 1 Copy to Conservation Division

RECEIVED  
OCT - 5 2012  
KCC DODGE CITY

Form: \_\_\_\_\_

RMJ