

KCC OIL/GAS REGULATORY OFFICES

Date: 10/08/12

District: 1

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 3842

API Well Number: 15-101-22400-00-00

Op Name: Larson Engineering, Inc. dba Larson Operating Company

Spot: NW-NW-SW-NW Sec 11 Twp 19 S Rng 29 E / W

Address 1: 562 W. State Rd. 4

1360 Feet from N / S Line of Section

Address 2: _____

122 Feet from E / W Line of Section

City: Olmitz

GPS: Lat: 38.42007 Long: 100.50216 Date: 10/8/12

State: KS Zip Code: 67564 -8561

Lease Name: Riemann-Suppe Well #: 1-11

Operator Phone #: (620) 653-7368

County: Jane

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

None.

Findings:

8 5/8" was set @ 260' with 175 sx cement. 5 1/2" was set @ 4657' with 125 sx cement on the primary cementing job.. Company opened the port collar @ 2129'. Swift Services, Inc. pumped 195 sx SMD cement, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None. Alternate II cementing requirements have been met.
SMD cement with 1/4# floreal by Swift Services, Inc.
GPS converted footages are 1348' FNL & 151' FWL.

Verification Sources:

Photos Taken: 0

<input type="checkbox"/> RBDMS	<input type="checkbox"/> KGS	<input type="checkbox"/> TA Program
<input type="checkbox"/> T-I Database	<input type="checkbox"/> District Files	<input type="checkbox"/> Courthouse
<input checked="" type="checkbox"/> Other: <u>On-site witness</u>		

By: *Eric McLaren*

Eric McLaren

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

OCT 10 2012

KCC DODGE CITY

RECEIVED

OCT 18 2012

KCC WICHITA

Form: _____

ATW