

KCC OIL/GAS REGULATORY OFFICES

Date: 10/05/12

District: 1

Case #: _____

☐ New Situation
☒ Response to Request
☐ Follow-Up

☐ Lease Inspection
☐ Complaint
☒ Field Report

Operator License No: 4767

API Well Number: 15-083-21846-00-00

Op Name: Ritchie Exploration, Inc.

Spot: SW-NE-SE Sec 32 Twp 24 S Rng 24 ☐ E / ☒ W

Address 1: Box 783188

1765 Feet from ☐ N / ☒ S Line of Section

Address 2: _____

945 Feet from ☒ E / ☐ W Line of Section

City: Wichita

GPS: Lat: 37.91798 Long: 99.97643 Date: 10/5/12

State: KS Zip Code: 67278 -3188

Lease Name: Rebein Well #: 1

Operator Phone #: (316) 691-9500

County: Hodgeman

Reason for Investigation:

Company requested a state witness to the alternate II cementing job.

Problem:

Alternate II cementing requirements have not been met.

Persons Contacted:

Gary Rowe.

Findings:

2:15 p.m.
 8 5/8" was set @ 356' with 225 sx cement. 5 1/2" was set @ 5063' with 175 sx cement on the primary cementing job. Company opened the port collar @ 1583'. Basic Energy Services pumped 300 sx cement, with 200# of hulls, circulating 15 sx to the pit. Closed the port collar.

Action/Recommendations:

Follow Up Required ☐ Yes ☒ No ☐

Date: _____

None. Alternate II cementing requirements have been met.
 60/40 Pozmix, 4% gel by Basic Energy Services.
 GPS converted footages are 1787' FSL & 962' FEL.

Verification Sources:

Photos Taken: 0

☐ RBDMS ☐ KGS ☐ TA Program
☐ T-I Database ☐ District Files ☐ Courthouse
☒ Other: On-site witness.

By: Eric MacLaren
Eric MacLaren

Retain 1 Copy District Office
 Send 1 Copy to Conservation Division

RECEIVED

OCT 10 2012

KCC DODGE CITY

RECEIVED

OCT 18 2012

KCC WICHITA

Form: _____