

KCC OIL/GAS REGULATORY OFFICES

Date: 11/07/12

District: 01

Case #: _____

- New Situation
- Response to Request
- Follow-Up

- Lease Inspection
- Complaint
- Field Report

Operator License No: 4767

API Well Number: 15-057-20848-00-00

Op Name: Ritchie Exploration, Inc.

Spot: SW NE SW Sec 25 Twp 26 S Rng 23 E / W

Address 1: 8100 E 22nd St N #700

1798 (1798) Feet from N / S Line of Section

Address 2: BOC 783188

1538 (1547) Feet from E / W Line of Section

City: Wichita

GPS: Lat: 37.75396 Long: 99.79148 Date: 11/7/12

State: Kansas Zip Code: 67278 -3188

Lease Name: Nau 25C Well #: 1

Operator Phone #: (316) 691-9500

County: Ford

Reason for Investigation:

Company requested state witness for Alternate II cementing

Problem:

None

Persons Contacted:

None

Findings:

12:30pm

Surface Casing: 8.625" @ 372' w/ 225sx

Production Casing: 5.5 @ 5078' w/ 175sx

TD: 5090'

Port collar opened at 1425' Consolidated Oil Well Services pumped 225sx 60/40 pozmix, 6% gel, 1/4# Flo seal, 250# CSH with 20sx circulating to pit. Port Collar closed.

Action/Recommendations:

Follow Up Required Yes No

Date: _____

None

Verification Sources:

- RBDMS
- T-J Database
- Other: on-site witness
- KGS
- District Files
- TA Program
- Courthouse

Photos Taken: 0

By: Kenny Sullivan

Kenny Sullivan

Retain 1 Copy District Office
Send 1 Copy to Conservation Division

RECEIVED
NOV - 9 2012
KCC DODGE CITY

RECEIVED
NOV 14 2012
KCC WICHITA

Form: _____

AWK