

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21463-00-00
Spot: NWSENE Sec/Twnshp/Rge: 36-10S-17W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: WHISMAN Well #: 4
County: ROOKS Total Vertical Depth: 3506 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1130
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3504		100 SX
SURF	8.625	250		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/08/2013 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL CO. INC. Phone: (620) 793-2672

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.
Perforations at 3370' - 3392'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/08/2013 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

DS&W Well Service milled on well # 4 on 01/07/2013 to 1000'. Pulled tubing and bit.
01/08/2013-Ran in hole with bit stacked out on busted casing at 630'. Pulled tubing and bit.
Ran in hole with a notched collar and got to 1223'. Consolidated rigged to tubing and mixed
and pumped 250 sx 60/40 pozmix.
Pulled tubing to 770'. Pumped 35 sx with 250 # hulls mixed in to circulate cement up 4 1/2"
casing. Pulled tubing and topped off 4 1/2" casing with 10 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 5 sx cement to pressure with 150 psi and 150 psi shut in
pressure.

Perfs:

Top	Bot	Thru	Comments
3370	3392		
3272	3278		
3246	3252		
3224	3230		

RECEIVED
JAN 16 2013
KCC WICHITA

Remarks: CONSOLIDATED CEMENTING TICKET # 39273

Plugged through: TBG

District: 04

Signed [Signature] (TECHNICIAN) CM

JAN 10 2013