

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22346-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 1-35S-2E
4288 feet from S Section Line, 1375 feet from E Section Line
Lease Name: SUNDANCE Well #: 1
County: SUMNER Total Vertical Depth: 3210 feet

Operator License No.: 30253
Op Name: CYCLONE PETROLEUM, INCORPORAT
Address: 1030 W. MAIN
JENKS, OK 74037

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3208		225 SX
SURF	8.625	266		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/31/2012 8:00 AM
Plug Co. License No.: 33556 Plug Co. Name: DRAKE EXPLORATION, LLC
Proposal Rcvd. from: DARREN BROYLES Company: DRAKE EXPLORATION Phone: (620) 441-7223

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/31/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @1550', DUMP BAILED 2 SXS CEMENT ON TOP.
PRESSURED CASING @ 100#, HELD OK. RIH ON WIRELINE SHOT SQUEEZE HOLES
@ 313'-315' (5 HOLES). SWEDGED INTO 4 1/2" CASING, CONSOLIDATED MIXED &
PUMPED 100 SXS 60/44 POZMIX 2% CC TO SURFACE. CEMENT CIRCULATED.
PLUG DOWN 12-31-2012 5:00 PM. CEMENT TICKET #38402.

Perfs:

Top	Bot	Thru	Comments
3142	3152		CSG
1572	1574		CSG

RECEIVED
JAN 08 2013
KCC WICHITA

Remarks: PERFS @ 1850-1852 W/150 SXS, PERFS @ 1900 W/250 SXS
TA N.O.V. CYCLONE NO LONGER HAD O.G LOGS. LEFT WELL ASD.
Plugged through: TBG

District: 02

Signed

Duane Krueger
9/01/12
(TECHNICIAN)

12