

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15249-00-00
Spot: S2SESE Sec/Twnshp/Rge: 4-17S-11W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: RIEMANN J Well #: 1
County: BARTON Total Vertical Depth: 3297 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3291		125 SX
SURF	10.75	286		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/07/2013 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: CURTIS R LONGPINE Company: DAMAR RESOURCES Phone: (785) 625-0025

Proposed Plugging Method: Well has tubing stuck in hole at 1700'. Will cut tubing and plug from there.
Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/07/2013 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Cut off tubing at 1670'. Pulled tubing up to 1450' and perforated.
Ran tubing back down to 1640' and pumped 100 sx cement.
Pulled tubing to 700' and perforated.
Ran tubing to 730'. Circulated cement to surface with 80 sx cement. Shut in pressure at 300 psi.
Surface pipe had been squeezed from 250' to surface.

GPS: 38.59529 -098.53764

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: ESOTB

District: 04

Signed Bruce Rodie
2/07/13 (TECHNICIAN)

CM

RECEIVED
JAN 16 2013
KCC WICHITA

JAN 10 2013