

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-21867-00-00  
Spot: SENENWSW Sec/Twnshp/Rge: 24-23S-23W  
2279 feet from S Section Line, 1003 feet from W Section Line  
Lease Name: SHARON Well #: 2-24  
County: HODGEMAN Total Vertical Depth: 4682 feet

Operator License No.: 32331  
Op Name: DK OPERATING INC.  
Address: 24583 NW 208 RD  
JETMORE, KS 67854

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	240		WITH 150 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/22/2012 12:00 PM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Rcvd. from: WALT PURCELL Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE  
Date/Time Plugging Completed: 12/22/2012 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 700' WITH 80 SX CMT. 3RD PLUG AT 270' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
JAN 07 2013  
KCC WICHITA

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
JAN - 2 2013  
KCC DODGE CITY