

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20138-00-00  
Spot: N2N2NE Sec/Twnshp/Rge: 6-33S-21W  
336 feet from N Section Line, 1253 feet from E Section Line  
Lease Name: RANDALL Well #: 1-6  
County: CLARK Total Vertical Depth: 5400 feet

Operator License No.: 5303  
Op Name: CANADAY OIL CORPORATION  
Address: 842 TOH-N-HAH TR  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4875		
CIBP		5200		
PROD	4.5	5396	2885	WITH 200 SX CMT
SURF	8.625	680		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2012 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: DUMP 2 SX CMT ON CIBP. PLUG AT 1170' WITH 12 SX GEL & 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/11/2012 3:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 4875' WITH 2 SX CMT. 1ST PLUG AT 1182' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 714' WITH 50 SX CMT. 3RD PLUG AT 324' WITH 30 SX CMT. 4TH PLUG AT 39' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5299	5308		
4908	4916		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

RECEIVED  
DEC 26 2012  
KCC WICHITA

District: 01

RECEIVED

DEC 19 2012

KCC DODGE CITY

Signed

*[Handwritten Signature]*  
12/26/12

(TECHNICIAN)

*[Handwritten Initials]*