

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21615-00-00
Spot: NESENWSW Sec/Twnshp/Rge: 1-22S-10W
1968 feet from S Section Line, 4140 feet from E Section Line
Lease Name: ALAN Well #: C-1
County: RENO Total Vertical Depth: 3700 feet

Operator License No.: 6768
Op Name: CARRIE EXPLORATION & DEVELOPM
Address: 210 W 22ND
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/03/2012 8:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JERRY Company: SOUTHWIND DRILLING Phone: (620) 617-1716

Proposed Plugging Method: 35 SX TOP OF ARBUCKLE, 35 SX 1300', 35 SX 850', 35 SX 310', 20 SX 60', 20 SX RAT HOLE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 12/04/2012 5:45 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

RAN DRILLING PIPE TO TOP OF ARBUCKLE AT 3560' & SPOTTED 35 SX CEMENT.
PULL DRILL PIPE TO 1300', SPOTTED 35 SX CEMENT, PULLED DRILL PIPE TO 850'
SPOTTED 35 SX CEMENT, PULLED DRILL PIPE TO 310', SPOTTED 35 SX CEMENT.
PULLED DRILL PIPE TO 60' & CIRCULATED CEMENT TO SURFACE. CIRCULATED
20 SX IN RAT HOLE.

Remarks: ALLIED CEMENT 60/40 4% GEL.

Plugged through: DP

District: 02

Signed _____

12/24/12 (TECHNICIAN)

RECEIVED
DEC 21 2012
KCC WICHITA