

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-30404-00-00
Spot: NWNENE Sec/Twnshp/Rge: 29-34S-7E
4651 feet from S Section Line, 853 feet from E Section Line
Lease Name: MINOR Well #: 2
County: COWLEY Total Vertical Depth: 2615 feet

Operator License No.: 33118
Op Name: ANSTINE, GARY DBA ANSTINE OIL CO
Address: 27630 21ST RD
GEUDA SPRINGS, KS 67051

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2574		
PROD	4.5	2613		50 SX
SURF	8.625	162		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2012 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: TREY CLAPP Company: C & C OIL CO. Phone: (620) 758-2476

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2550', ELMORES MIXED & PUMPED 6 BBL FLUSH W/2 SXS GEL, 10 SXS CLASS A COMMON CEMENT, & DISPLACED IN CSG W/3 BBL FLUSH W/ 1 SX GEL. WAITED 2 HOURS, TAGGED CEMENT @ 2214'. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 340', RIH W/TBG @ 350', ELMORES MIXED & PUMPED 110 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET # 10340. PLUG DOWN 12-6-2012, 5:00 PM.

Perfs:

Top	Bot	Thru	Comments
2578	2581	CSG	
2565	2569	CSG	

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

RECEIVED

DEC 17 2012

KCC WICHITA

District: 02

Signed

[Signature]
12/24/12 (TECHNICIAN)