

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22868-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 16-7S-20W
4290 feet from S Section Line, 4950 feet from E Section Line
Lease Name: RISELEY B Well #: 1
County: ROOKS Total Vertical Depth: 3685 feet

Operator License No.: 31569
Op Name: BACH, JASON DBA BACH OIL PRODUC
Address: PO BOX 723
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3360		135 SX
SURF	8.625	251		170 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2012 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DALE FERLAND Company: BACH OIL PRODUCTION Phone: (785) 302-1435

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Casing leak at 1000' - 1010'.
1600' to surface w/375 sx cement (ALT II)
Production Perforations: 3381' - 3644'.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2012 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3500' and pumped 80 sx cement w/175 # hulls.
Pulled tubing to 2500' and pumped 80 sx cement w/175 # hulls.
Pulled tubing to 1250' and pumped 75 sx cement to circulate to surface.
Pulled all tubing and topped off 4 1/2" casing w/25 sx cement.
Hooked to 8 5/8" x 4 1/2" annulus. Pressured up immediately.

Perfs:

Top	Bot	Thru	Comments
3632	3644		
3397	3400		
3381	3383		

Remarks: ALLIED CEMENTING TICKET # 53950

Plugged through: TBG

RECEIVED
DEC 11 2012

KCC WICHITA

District: 04

Signed Pat Bedore
12/20/12 (TECHNICIAN)

cm

DEC 07 2012