

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24268-00-01
Spot: NWSESESW Sec/Twnshp/Rge: 7-13S-20W
468 feet from S Section Line, 3267 feet from E Section Line
Lease Name: KOHL Well #: 7A
County: ELLIS Total Vertical Depth: 4000 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3948		175 SX
SURF	8.625	1515		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2012 11:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TERRY PIESKER Company: DOWNING NELSON OIL CO INC. Phone: (785) 735-4363

Proposed Plugging Method: Ordered 655 sx 60/40 pozmix 4% gel cement w/600 # hulls and 10 sx gel. PBTD 3815'.
Perforations at 3640' - 3644', 3615' - 3619', 3592' - 3596', 3512' - 3515', 3495' - 3498', 3468' - 3470'. Squeezed off 3640' - 3644', 3615' - 3619', 3592' - 3596' with 150 sx cement.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2012 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perforated at 1475'.
Ran in hole with tubing to 3606'. Rigged to tubing and pumped 10 sx gel followed by 75 sx cement w/200 # hulls.
Pulled tubing to 2070'. Rigged to tubing and pumped 190 sx cement w/300 # hulls to circulate cement up 5 1/2" casing.
Pulled tubing. Topped 5 1/2" casing with 30 sx cement. Hole standing full.
Rigged to 8 5/8" casing and pumped 10 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

Perfs:


Top	Bot	Thru	Comments
3815			
3640	3644		
3615	3619		
3592	3596		
3512	3515		
3495	3498		
3468	3470		

Remarks: ALLIED TICKET # 56599

Plugged through: TBG

RECEIVED
JAN 07 2013
KCC WICHITA

District: 04

Signed  (TECHNICIAN) CM

DEC 27 2012