

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-23944-00-00  
Spot: SWSNW Sec/Twnshp/Rge: 16-30S-7E  
2978 feet from S Section Line, 3681 feet from E Section Line  
Lease Name: SCHULZ Well #: 3  
County: COWLEY Total Vertical Depth: 3260 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3253		100 SX
SURF	8.625	301		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/22/2012 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM, LLC Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND BACK 50' ABOVE OPEN HOLE, CAP W/5 SKS. CUT CASING, CIRCUALTE FROM 350'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/09/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE OPEN HOLE @ 3200', DUMP BAILED 5 SXS CEMENT ON TOP. CUT CASING @ 1,111', POOH W/1, 111' (32 JOINTS) 5 1/2" CASING. 12-7-2012, RIH W/TBG @ 360', COPELAND ACID ESTABLISHED CIRCULATION, MIXED & PUMPED 125 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 12-9-2012. COPELAND CEMENT TICKET #41740.

Perfs:

Top	Bot	Thru	Comments
3253	3260	OH	


RECEIVED  
DEC 17 2012

Remarks:

Plugged through: TBG

District: 02

Signed

  
12/17/12 (TECHNICIAN)

KCC WICHITA