

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-165-21069-00-01  
Spot: SWNENW Sec/Twnshp/Rge: 11-16S-17W  
990 feet from N Section Line, 1650 feet from W Section Line  
Lease Name: YOUNGER Well #: 1  
County: RUSH Total Vertical Depth: 3560 feet

Operator License No.: 32875  
Op Name: BOWLES, C. W. DBA CWB - CO.  
Address: PO BOX 186  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3560	2215	WITH 150 SX CMT
SURF	8.625	1132		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/11/2012 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY OIL WELL CEMENTING Phone: (620) 727-3410

Proposed Plugging Method: SAND TO 3411' & 2 SX CMT. PLUG AT 1170' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE  
Date/Time Plugging Completed: 12/11/2012 6:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SAND TO 3411' & 4 SX CMT. 1ST PLUG AT 1170' 10 SX GEL. NO CIRCULATION. PUMPED 15 SX GEL, 800# HULLS, & 50 SX CMT. WAIT 2 HOURS. TAGGED PLUG. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3495			
3493			
3461	3495		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE

Plugged through: CSG

RECEIVED  
DEC 20 2012  
KCC WICHITA

District: 01

RECEIVED  
DEC 14 2012  
KCC DODGE CITY

Signed Kenny Sullivan  
12/11/12 (TECHNICIAN)

R40