

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20774-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 18-32S-5E  
202 feet from S Section Line, 4605 feet from E Section Line  
Lease Name: BARNETT Well #: 2  
County: COWLEY Total Vertical Depth: 2450 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L.  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2445	578	75 SX
SURF	8.625	150		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2012 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L.  
Proposal Rcvd. from: ALBERT COOPER Company: COOPER SERVICE COMPANY Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/07/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2411', TAGGED SOLID. LAYED DOWN TBG. SANDED BACK @ 2290', DUMP BAILED 5 SXS CEMENT ON TOP. TAGGED BOTTOM CEMENT PLUG @ 2242', 12-3-2012, CUT CASING @ 578', LAYED DOWN CASING. 12-7-2012, RIH W/TBG @ 275', COPELAND ACID SERVICE ESTABLISHED CIRCULATION. MIXED & PUMPED 95 SXS 60/40 POZMIX 4% GEL TO SURFACE, LAYED DOWN TBG. CEMENT CIRCULATED. PLUG DOWN 12-7-2012 @ 5:00 PM. COPELAND ACID SERVICE CEMENT TICKET #41738.

Perfs:


Top	Bot	Thru	Comments
2354	2360	CSG	LAYTON

Remarks: COMPLIANCE PLUGGING/ TA

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

RECEIVED  
DEC 17 2012  
KCC WICHITA