

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22769-00-00
Spot: SENESE Sec/Twnshp/Rge: 13-12S-23W
2140 feet from S Section Line, 160 feet from E Section Line
Lease Name: KD UNIT Well #: 1-13
County: TREGO Total Vertical Depth: 4204 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4203	1026	
SURF	8.625	224		170 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/30/2012 8:15 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: TERRY PEISKER Company: DOWNING-NELSON OIL CO Phone: (785) 735-4363

Proposed Plugging Method: Ordered 525 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Hole has 3177' of 5 1/2" casing and port collar. Cut off at 2500'. Shot at 1624' and 1026'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2012 5:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing at 2500'. Pulled casing to 2260' and pumped 125 sx cement w/300 # hulls.. Could not pull casing.
Cut casing at 1800'. Could not pull casing.
Shot casing at 1026'. Could not pull casing. Pumped 40 sx cement and displaced to bottom.
Shot casing at 1026' and pulled to 900'. Pumped 80 sx cement w/200 # hulls.
Pulled casing to 225' and pumped 100 sx cement. Circulated cement to cellar. POOH and cellar stayed full.

GPS: 39.00695 -099.81674

Perfs:

Top	Bot	Thru	Comments
3911	3914		
3782	3786		
3762	3766		
3749	3751		
3748	3752		
3709	3711		

Remarks: QUALITY WELL SERVICE TICKET # 5758

Plugged through: CSG

District: 04

Signed Ray Dinkel
12/27/12 (TECHNICIAN)

CM

DEC 03 2012

RECEIVED
DEC 10 2012
KCC WICHITA