

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23137-00-00
Spot: NESWSW Sec/Twnshp/Rge: 13-16S-26W
1005 feet from S Section Line, 4353 feet from E Section Line
Lease Name: EVEL A Well #: 1
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 33984
Op Name: LUTZ, SCOTT T. TRUST
Address: 1645 W. SUNRISE MOUNTAIN RD PO
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4500		WITH 2 SX CMT
PROD	5.5	4601	0	WITH 200 SX CMT
SURF	8.625	324		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/26/2012 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEN RUPP Company: SCOTT T. LUTZ TRUST Phone: (785) 798-5260

Proposed Plugging Method: RUN BOND LOG & FIND CMT. SET CIBP ON BOTTOM & 2 SX CMT. IF THERE IS NOT CMT ON BACKSIDE PERFORATE CASING AT PERMIAN. PUMP 80 SX CMT OVER CASING VOLUME IF DOES NOT CIRCULATE, 150 SX CMT FOR BACKSIDE. IF CMT ON BACKSIDE, RUN TBG TO ANHYDRITE & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 11/26/2012 5:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4500' WITH 2 SX CMT. LOAD HOLE & RUN BOND LOG. FOUND CMT FROM TOP TO 2000'. RUN TBG TO 2026' & PUMPED 235 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 35 SX CMT. TIED ONTO BACKSIDE & PUMPED 1/4 BBL. PRESSURED TO 500# & HELD.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED
DEC 17 2012
KCC WICHITA

District: 01

Signed Melvin J. Maier
11/27/12 (TECHNICIAN)

RECEIVED

DEC -7 2012

KCC DODGE CITY

AMC