

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23159-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 13-16S-26W  
2305 feet from S Section Line, 4346 feet from E Section Line  
Lease Name: EVEL A Well #: 2  
County: NESS Total Vertical Depth: 4580 feet

Operator License No.: 33984  
Op Name: LUTZ, SCOTT T. TRUST  
Address: 1645 W. SUNRISE MOUNTAIN RD. PO  
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4347		WITH 2 SX CMT
PROD	5.5	4599	0	WITH 320 SX CMT
SURF	8.625	337		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2012 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEN RUPP Company: SCOTT T. LUTZ TRUST Phone: (785) 798-5260

Proposed Plugging Method: SET CIBP THEN RUN BOND LOG. IF CMT IS DOWN TO 2000' RUN TBG & CIRCULATE. IF NOT, THEN PERFORATE AT ANHYDRITE & PUMP 50 SX CMT. PUMP 80 SX CMT OVER CASING VOLUME AT PERMIAN. IF DOES NOT CIRCULATE, PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2012 2:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4347' WITH 2 SX CMT. LOADED CASING & RUN BOND LOG. FOUND CMT DOWN TO 2300'. RUN TBG TO 2026' & PUMPED 200 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 40 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier  
12/27/12 (TECHNICIAN)

RECEIVED  
DEC -7 2012  
KCC DODGE CITY

RECEIVED  
DEC 17 2012  
KCC WICHITA