

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23439-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 13-16S-26W  
1682 feet from S Section Line, 4978 feet from E Section Line  
Lease Name: EVELA Well #: 5  
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 33984  
Op Name: LUTZ, SCOTT T. TRUST  
Address: 1645 W. SUNRISE MOUNTAIN RD. PO  
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3630		WITH 2 SX CMT
PROD	5.5	4604	0	WITH 210 SX CMT
SURF	8.625	397		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2012 12:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: KEN RUPP Company: SCOTT T. LUTZ TRUST Phone: (785) 798-5260

Proposed Plugging Method: SET CIBP ON BOTTOM WITH 2 SX CMT. RUN TBG TO 2000' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2012 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3630' WITH 2 SX CMT. RUN TBG TO 2026' & PUMPED 210 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 35 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

RECEIVED  
DEC 17 2012  
KCC WICHITA

District: 01

Signed Michael Maier  
12/27/12 (TECHNICIAN)

RECEIVED  
DEC -7 2012  
KCC DODGE CITY