

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19526-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 7-29S-6E
311 feet from S Section Line, 5172 feet from E Section Line
Lease Name: FRENCH Well #: 1
County: BUTLER Total Vertical Depth: 2850 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2836	945	0 SX
SURF	8.625	157		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/10/2012 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: According to KCC Rules & Regulations

Plugging Proposal Received By: DUANE KRUEGER
Date/Time Plugging Completed: 12/12/2012 5:00 PM

Witness Type: PARTIAL
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2785', DUMP BAILED 6 SXS CEMENT ON TOP. 12-11-2012, CUT CASING @ 945', LAYED DOWN 5-1/2" CASING. 12-12-2012, RIH W/TBG @ 260', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12-12-2012, 5:00 PM. CONSOLIDATED CEMENT TICKET #35395.

Perfs:

Top	Bot	Thru	Comments
2836	2850	OH	

RECEIVED
DEC 26 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed [Signature]
12/19/12 (TECHNICIAN)