

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01006-00-01
Spot: SWNESWSW Sec/Twnshp/Rge: 7-29S-6E
981 feet from S Section Line, 4574 feet from E Section Line
Lease Name: FRENCH OWWO Well #: 3
County: BUTLER Total Vertical Depth: 2903 feet

Operator License No.: 32475
Op Name: BRADEN, JAMES R. DBA BRADEN PET
Address: 10139 SW HAVERHILL RD
AUGUSTA, KS 67010

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2903		0 SX
SURF	8.625	154		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2012 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (620) 222-1252

Proposed Plugging Method: According to KCC Rules & Regulations

Plugging Proposal Received By: DUANE KRUEGER
Date/Time Plugging Completed: 12/12/2012 5:00 PM

Witness Type: PARTIAL
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK 50' ABOVE PERFS @ 2790', DUMP BAILED 4 SXS CEMENT ON TOP. 12-12-2012, RIH INSIDE 4-1/2" CSG W/2-3/8" TBG @ 260', & RIH W/1" TBG ON BACKSIDE OF 4.5" CSG @ 42'. SWEDGED INTO 2-3/8" TBG & CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. SWEDGED INTO 1" TBG & CONSOLIDATED MIXED & PUMPED 30 SXS 60/40 POXMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. LAYED DOWN 2-3/8' & 1" TBG. TOPPED WELL BACK TO SURFACE W/10 SXS. PLUG DOWN 12-12-2012, 5:00 PM. CONSOLIDATED CEMENT TICKET #35396. TOTAL 80 SXS 60/40 POZMIX 4% GEL ON TOP PLUG.

Perfs:

Top	Bot	Thru	Comments
2842	2854	CSG	


RECEIVED
DEC 26 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed


12/27/12 (TECHNICIAN)

JK