

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21507-00-00
Spot: E2SE Sec/Twnshp/Rge: 2-24S-15W
1463 feet from S Section Line, 682 feet from E Section Line
Lease Name: MUNZ Well #: 1
County: STAFFORD Total Vertical Depth: 4129 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, L
Address: PO BOX 164
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4128	0	WITH 125 SX CMT
SURF	8.625	259		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2012 8:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: HAROLD BELLERIVE Company: _____ Phone: (785) 635-4531

Proposed Plugging Method: SET CIBP @ 4040' WITH 2 SX CMT ON TOP. PERFORATE CASING @ 980'. CIRCULATE CMT TO SURFACE UP SURFACE PIPE & CASING.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/12/2012 11:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

COULDN'T GET TBG PAST 2400' DUE TO CASING FAILURE. RAN TBG TO 2365' & PUMPED 30 SX CMT. PERFORATED CASING AT 980'. RAN TBG TO 990'. PUMPED 400 SX CMT DOWN TBG. CIRCULATED CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS. PULLED TBG OUT OF HOLE & TOPPED OFF WITH 8 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4094	4108		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
12/24/12 (TECHNICIAN)

RECEIVED

DEC 14 2012

KCC DODGE CITY

RECEIVED
DEC 17 2012
KCC WICHITA

BWZ