

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20209-00-00  
Spot: NENESE Sec/Twnshp/Rge: 27-24S-16W  
2310 feet from S Section Line, 330 feet from E Section Line  
Lease Name: SCHMITT Well #: 1  
County: EDWARDS Total Vertical Depth: 4392 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4391	1304	WITH 75 SX CMT
SURF	8.625	297		225 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/06/2012 2:30 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: PUMP 50 SX CMT @ 4200' THROUGH TBG. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/06/2012 5:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

\*\*CASING LEAK @ 1600' WAS SQUEEZED WITH 200 SX CMT.\*\* PUMPED 50 SX CMT & 300# HULLS @ 4200' THROUGH TBG. TAGGED TOP OF CEMENT AT 3400'. 1ST PLUG AT 1088' WITH 4 SX GEL & 50 SX CMT. 2ND PLUG AT 340' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4253	4282		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

RECEIVED  
DEC 13 2012  
KCC WICHITA

District: 01

Signed Richard W. Lacey  
12/29/12 (TECHNICIAN)

RECEIVED  
DEC -7 2012  
KCC DODGE CITY