

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-057-20862-00-00  
Spot: S2SWNW Sec/Twnshp/Rge: 12-27S-24W  
2676 feet from N Section Line, 680 feet from W Section Line  
Lease Name: FORD YARD-KSR Well #: 1  
County: FORD Total Vertical Depth: 2780 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	351		WITH 225 SX CMT

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/10/2012 11:15 PM  
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.  
Proposal Rcvd. from: MIKE GODFREY Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 840' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE  
Date/Time Plugging Completed: 12/11/2012 1:15 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

\*\*LEFT DRILL COLLARS IN HOLE. TOF @ 2334'.\*\* 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 840' WITH 80 SX CMT. 3RD PLUG AT 390' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED  
DEC 17 2012  
KCC WICHITA

District: 01

RECEIVED  
DEC 13 2012

Signed K. M. [Signature]  
12/29/12 (TECHNICIAN)

KCC DODGE CITY

*AMW*