

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20603-00-00
Spot: NENESESW Sec/Twnshp/Rge: 11-17S-31W
1318 feet from S Section Line, 2914 feet from E Section Line
Lease Name: HUSEMAN 11C Well #: 1
County: SCOTT Total Vertical Depth: 4615 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		2269		WITH 425 SX CMT
PROD	4.5	4610	0	WITH 235 SX CMT
SURF	8.625	211		WITH 170 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2012 9:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 300# HULLS. PULL TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & MIX 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2012 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4383' & PUMP 50 SX CMT & 300# HULLS. PULL TBG TO 2213' & PUMPED 160 SX CMT. CMT CIRCULATED. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4563	4569		
4390	4395		
4362	4395		
3950	3954		

RECEIVED
DEC 21 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

RECEIVED
DEC 18 2012
KCC DODGE CITY

Signed Michael Maier
12/28/12 (TECHNICIAN)

ROWE