

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-23800-00-02  
Spot: NWSENESE Sec/Twnshp/Rge: 30-19S-21W  
1651 feet from S Section Line, 353 feet from E Section Line  
Lease Name: MOORE HEIRS D Well #: 2  
County: NESS Total Vertical Depth: 4428 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PC	5.5	1494		WITH 250 SX CMT
PROD	5.5	4413	0	WITH 100 SX CMT
SURF	8.625	309		WITH 180 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/05/2012 1:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SCOTT BOEH Company: RITCHIE EXPLORATION Phone: (620) 617-4671

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & MIX 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/06/2012 11:55 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4385' & PUMP 50 SX CMT & 150# HULLS. PULL TBG TO 1526' & PUMP 195 SX CMT & 400# HULLS. LOST CIRCULATION. PULLED TBG & SHUT DOWN UNTIL MORNING. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD. 12/6/12: RAN IN WITH SANDLINE & FOUND CMT AT 1300'. RUN TBG TO 1250' & PUMPED 116 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4422	4438		
4413	4422		MISSISSIPPIAN
4329	4332		FT SCOTT

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Michael Maier  
12/07/12 (TECHNICIAN)

RECEIVED  
DEC -7 2012  
KCC DODGE CITY

RECEIVED  
DEC 17 2012  
KCC WICHITA

802