

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30847-00-00
Spot: NWNESW Sec/Twnshp/Rge: 26-18S-11W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: AMES UNIT Well #: 1
County: BARTON Total Vertical Depth: 3327 feet

Operator License No.: 30458
Op Name: RJM COMPANY
Address: PO BOX 256
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		
CIBP		3190		
PROD	5.5	3313		100 SX
SURF	8.625	190		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2012 9:00 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Revd. from: CHRIS HOFFMAN Company: RJM CO Phone: (620) 587-3600

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Junk in hole at 2965'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1250', 530' and 180'.
Ran tubing to 2960' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls.
Pulled tubing to 1250' and pumped 70 sx cement w/100 # hulls.
Pulled tubing to 530'. Circulated cement to surface with 100 sx cement and 100 # hulls.
Pulled tubing and topped off well with 10 sx cement.
Tied to surface pipe and pressured up to 300 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
3313	3327		ARBUCKLE OH
3280	3313		
3212	3215		LKC
3180	3188		LKC
3090	3096		LKC
3054	3188		LKC

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

RECEIVED
DEC 11 2012
KCC WICHIT.

District: 04

Signed Bruce Rodie
12/20/12 (TECHNICIAN) CM

DEC 08 2012