

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23720-00-00  
Spot: SWNENWNE Sec/Twnshp/Rge: 35-9S-23W  
335 feet from N Section Line, 1688 feet from E Section Line  
Lease Name: WAHRMAN Well #: 1  
County: GRAHAM Total Vertical Depth: 3965 feet

Operator License No.: 33823  
Op Name: SENTINEL PETROLEUM, INC.  
Address: 101 N ROBINSON STE 910  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3963		150 SX
SURF	8.625	266		165 SX
TI	2.375	3928		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/07/2012 8:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Revd. from: DENNIS ANGLIN Company: SENTINEL Phone: (405) 206-9191

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.  
DV tool at 2018' w/190 sx cement.  
Perforations at 3842' - 3846' and 3880' - 3886'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/07/2012 10:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3875' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls.  
Pulled tubing to 2200' and pumped 200 sx cement. Good circulation of cement.  
Pulled tubing out. Topped off with 20 sx cement.  
Tied on to back side and squeezed with 10 sx cement. Shut in pressure 300 psi.

GPS: 39.23292 -099.85344

Perfs:

Top	Bot	Thru	Comments
3880	3886		
3842	3846		

RECEIVED  
DEC 17 2012

Remarks: ALLIED CEMENTING TICKET # 56483

KCC WICHITA

Plugged through: TBG

District: 04

Signed [Signature]  
12/29/12 (TECHNICIAN)

CM

DEC 11 2012