

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-069-20415-00-00
Spot: NESWNWSE Sec/Twnshp/Rge: 12-27S-29W
1784 feet from S Section Line, 2231 feet from E Section Line
Lease Name: MILLER TRUST Well #: 1-12
County: GRAY Total Vertical Depth: 5198 feet

Operator License No.: 33650
Op Name: WEST BAY EXPLORATION CO.
Address: 13685 S WEST BAY SHORE # 200
TRAVERSE CITY, MI 49684

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1787		WITH 275 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/04/2012 2:00 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: WALT PURCELL Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: NONE
Date/Time Plugging Completed: 12/04/2012 4:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

1ST PLUG AT 1830' WITH 50 SX CMT. 2ND PLUG AT 810' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED

DEC -7 2012

KCC DODGE CITY

Signed

Kenny Sullivan
12/20/12
(TECHNICIAN)

RECEIVED
DEC 13 2012
KCC WICHITA

AMZ