

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21083-00-00 ** FOR IMAGING ONLY - WELL CANNOT BE INV'D. AS PLUG*
Spot: N2NWNE Sec/Twnshp/Rge: 3-24S-4W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease Name: SYMNS Well #: 1 *PT. EXCEEDS 5 YR. CUTOFF.*
County: RENO Total Vertical Depth: 3630 feet

Operator License No.: 5611
Op Name: LONNY BRUCE OPERATIONS, L.L.C.
Address: 2049 14TH AVE
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3400		
COND	12.75	225	0	175 SX CMT
PROD	5.5	3628	2420	150 S XCMT
SURF	8.625	598	0	150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2004 12:00 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LONNY BRUCE Company: _____ Phone: (620) 241-2938

Proposed Plugging Method: SAND OFF PERFS, PUT 5 SX CMT ON SAND, SHOOT AND PULL CASING, PUT IN CMT PLUGS PER STATE REQUIREMENT. BUILD BRIDGE IN 8-5/8, FILL TO SURFACE WITH CMT.

Plugging Proposal Received By: JEFF KLOCK WitnessType: NONE
Date/Time Plugging Completed: 12/16/2004 12:00 AM KCC Agent: JEFF KLOCK

Actual Plugging Report:

FOUND TD AT 3400. SANDED OFF TO 3290' AND DUMPED 5 SACKS OF CEMENT. RIP 5.5 AT 2420' PULLED TO 650' BROKE CIRCULATION, SPOTTED 35 SACKS CEMENT. FOUND CEMENT AT 60', PULLED CASING TO 60' AND CIRCULATED CEMENT TO SURFACE. PULLED THE REST OF THE CASING. HAVEN REDI MIX OUT TO TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3594	3594		
3340	3356		

RECEIVED
JAN 31 2013

Remarks:

Plugged through: CSG

KCC WICHITA

District: 02

Signed Jeff Klock
(TECHNICIAN)