

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-21040-00-00
Spot: S2S2NWSE Sec/Twnshp/Rge: 8-35S-30W
1400 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ADAMS Well #: 1-8
County: MEADE Total Vertical Depth: 6420 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 1601 NW EXPRESSWAY, STE 1300
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4620		WITH 2 SX CMT
PROD	5.5	5943	2503	WITH 260 SX CMT
SURF	8.625	1657		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2012 12:30 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP BOTTOM PLUG DOWN 5 1/2" CASING WITH 200# HULLS & 25S X CMT. PLUG AT 1680' WITH 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 12/04/2012 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4620' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
LOAD HOLE WITH MUD. 1ST PLUG AT 1680' WITH 50 SX CMT. 2ND PLUG AT 600'
WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4674	4677		
4648	4694		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Stephen J Pfeifer
12/04/12 (TECHNICIAN)

RECEIVED

DEC -7 2012

KCC DODGE CITY

RECEIVED
DEC 17 2012

KCC WICHITA

[Handwritten mark]