

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-30287-00-00  
Spot: S2S2NE Sec/Twnshp/Rge: 32-15S-11W  
2970 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: BORRELL B Well #: 8  
County: RUSSELL Total Vertical Depth: 3315 feet

Operator License No.: 31086  
Op Name: RICHLAN DRILLING, A GENERAL PAR  
Address: 598 2ND AVE  
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3310		125 SX
SURF	8.625	207		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2012 9:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: RICK SCHREIBER Company: RICHLAN DRILLING Phone: (620) 793-2032

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Packer stuck in well at 1407'. Will plug.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 640' and 190'.  
Ran tubing to 1340'. Tied to tubing and pumped 50 sx cement.  
Pulled tubing to 650' and pumped 40 sx cement. Cement circulated out casing.  
Shut in casing. Circulated cement out surface pipe with 90 sx cement.  
Pulled tubing and topped of with 30 sx cement. Pressured to 200 psi. Shut in.

GPS: 38.70691 -098.56834

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSGT

District: 04

Signed Bruce Rodie  
12/27/12 (TECHNICIAN)

CM

RECEIVED  
DEC 11 2012  
KCC WICHITA

DEC 08 2012