

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20920-00-00  
Spot: S2 Sec/Twnshp/Rge: 7-18S-34W  
1323 feet from S Section Line, 2553 feet from W Section Line  
Lease Name: KRAUSE Well #: 1-7  
County: SCOTT Total Vertical Depth: 5175 feet

Operator License No.: 5214  
Op Name: LARIO OIL & GAS COMPANY  
Address: 301 S MARKET ST  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	346		WITH 225 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/09/2012 9:40 PM  
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.  
Proposal Rcvd. from: MIKE KERN Company: PICKRELL DRILLING COMPANY, I Phone: (316) 262-8427

Proposed Plugging Method: 1ST PLUG AT 2470' WITH 50 SX CMT. 2ND PLUG AT 1400' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE  
Date/Time Plugging Completed: 12/09/2012 11:40 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 2470' WITH 50 SX CMT. 2ND PLUG AT 1400' WITH 80 SX CMT. 3RD PLUG AT 750' WITH 40 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

District: 01

RECEIVED

DEC 13 2012

KCC DODGE CITY

Signed

Michael Maier  
12/27/12 (TECHNICIAN)

RECEIVED  
DEC 20 2012  
KCC WICHITA

AWD